

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/RD/WORK_INDENT24412

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Improvements to Roads and Drains Sonnappa Layout Cross Roads Virupakshapura in Ward No. 09 (Vidyaranyapura) Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N LOKANATHREDDY	
				In Figures	In Words
1	279.9	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	cum	193.0	Rupees One Hundred Ninety Three Only
2	46.65	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5004.0	Rupees Five Thousand Four Only
3	97.97	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.)	cum	6044.78	Rupees Six Thousand Forty Four and Seventy Eight Paise Only
4	746.4	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications.	Sqm	301.26	Rupees Three Hundred One and Twenty Six Paise Only
5	5.88	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 500	Tonne	57630.0	Rupees Fifty Seven Thousand Six Hundred Thirty Only
6	279	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge	Sqm	1707.0	Rupees One Thousand Seven Hundred Seven Only

N.22018

Signature of the Contractor

N. Lokanathreddy
 Executive Engineer
 Byarayanapura Division
 BBMP, Bangalore - 92

Sum
 13/03